

Langford Engineering, Inc.
Project No. 113-054, Contract No. 1

All Bidders 60 Days

			Kingsley Constructors, Inc. The Woodlands, Texas 5% B.B.		Lewis Contractors, Inc. Bertram, Texas 5% B.B.	
			Unit	Total	Unit	Total
Base Bid Items						
1.	Erosion/Sediment Control Inside Treaschwig Right-Of-Way	1 L.S.	\$ 145.00	\$ 145.00	\$ 2,000.00	\$ 2,000.00
2.	Erosion/Sediment Control, Inside Treschwig Joint Powers Board Property	1 L.S.	\$ 692.00	\$ 692.00	\$ 2,000.00	\$ 2,000.00
3.	Traffic Control for Installation of Proposed Sanitary Sewer Manholes, Sanitary Sewer Line, Existing Manhole Top Removal, Existing Sanitary Sewer Plug and Fill, and Bypass Pumping Operations	1 L.S.	\$ 3,550.00	\$ 3,550.00	\$ 6,000.00	\$ 6,000.00
4.	24" PVC Sanitary Sewer (SDR 26), ASTM D3034, Includes all Fittings, Auger/Bore Construction, All Depths	222 L.F.	\$ 475.00	\$ 105,450.00	\$ 750.00	\$ 166,500.00
5.	24" PVC Sanitary Sewer (SDR 26), ASTM D3034, Includes all Fittings and 18' Restrained Joint Section, Auger/Bore Construction with 32" Steel Casing, 3/8" Minimum Thickness	83 L.F.	\$ 510.00	\$ 42,330.00	\$ 800.00	\$ 66,400.00
6.	Relocation of Traffic Control Box, Including Signal Wire Re-Route in 3" Conduit Down Outside of Existing Signal Pole, Power Re-Route from Bottom of Existing Breaker Box, Sensor Line Splice and Reroute, Concrete Foundation for TCB	1 L.S.	\$ 9,200.00	\$ 9,200.00	\$ 10,000.00	\$ 10,000.00
7.	Removal of 5' Concrete Manhole (Manhole #5) in Treaschwig Right-Of-Way	1 L.S.	\$ 3,200.00	\$ 3,200.00	\$ 3,000.00	\$ 3,000.00
8.	Removal of 5' Concrete Manhole (Manhole #1) in Treschwig Joint Powers Board Property	1 L.S.	\$ 3,200.00	\$ 3,200.00	\$ 3,000.00	\$ 3,000.00
9.	By-Pass Pumping, Including Mobilization, Set Up, Demobilization of Pump(s), Piping, Power Generation Equipment, Stand-by Pump(s), Piping, Power Generation Equipment as Needed for 24-Hour/Day Bypass Pumping as Described in Plans and Specifications	1 L.S.	\$ 43,000.00	\$ 43,000.00	\$ 15,000.00	\$ 15,000.00
10.	Precast Concrete Sanitary Sewer Manhole (Manhole #5A), 5' Diameter, Vented and Sealed, All Depths	1 L.S.	\$ 12,100.00	\$ 12,100.00	\$ 10,000.00	\$ 10,000.00

Langford Engineering, Inc.
Project No. 113-054, Contract No. 1

All Bidders 60 Days

			Kingsley Constructors, Inc. The Woodlands, Texas 5% B.B.		Lewis Contractors, Inc. Bertram, Texas 5% B.B.	
			Unit	Total	Unit	Total
11.	Precast Concrete Sanitary Sewer Manhole (Manhole #5), 5' Diameter Vented and Sealed	1 L.S.	\$ 11,050.00	\$ 11,050.00	\$ 25,000.00	\$ 25,000.00
12.	Precast Concrete Sanitary Sewer Manhole (Manhole #1), 5' Diameter	1 L.S.	\$ 11,600.00	\$ 11,600.00	\$ 25,000.00	\$ 25,000.00
13.	Drop Connection for 24" Gravity Sanitary Sewer (Manhole #5)	1 Ea.	\$ 9,800.00	\$ 9,800.00	\$ 8,000.00	\$ 8,000.00
14.	Trench Safety System for Auger/Bore Pits, All Depths and All Soil Types	50 L.F.	\$ 0.10	\$ 5.00	\$ 300.00	\$ 15,000.00
15.	Trench Safety System for 5' Diameter Precast Concrete Sanitary Sewer Manhole Installation	30 L.F.	\$ 0.10	\$ 3.00	\$ 100.00	\$ 3,000.00
16.	24" Sanitary Sewer Filled with Flowable Fill, Plugged and Abandoned in Place	620 L.F.	\$ 36.00	\$ 22,320.00	\$ 40.00	\$ 24,800.00
17.	Remove Top of Existing Concrete Manhole (Manholes #2, #3, and #4) to 4' Below Existing Grade and Fill with Bank Sand	3 Ea.	\$ 3,200.00	\$ 9,600.00	\$ 1,000.00	\$ 3,000.00
	Total Amount Base Bid (Bid Items 1 thru 17)			\$ 287,245.00		\$ 387,700.00
18.	Supplemental Items Extra Bank Sand	100 C.Y.	\$ 22.00	\$ 2,200.00	\$ 20.00	\$ 2,000.00
19.	Extra Cement-Stabilized Sand	100 C.Y.	\$ 25.00	\$ 2,500.00	\$ 25.00	\$ 2,500.00
	Subtotal Supplementary Items (Item Nos. 18 - 19)			\$ 4,700.00		\$ 4,500.00
	Total Amount Bid			\$ 291,945.00		\$ 392,200.00
	Bids Tabulated By: GLH Bid Tab Created By: LMM					